

# CITY OF BIXBY

P.O. Box 70  
116 W. Needles Ave.  
BIXBY, OK 74008  
(918) 366-4430  
(918) 366-6373 (fax)

## ADDENDUM NO. 5

**March 3, 2021**

To: All Bidders

Project: ***Haikey Creek 2019 Flood Damage Rehabilitation  
Project – Project No. FM29-2001***

Subject: Answers to Questions

---

THIS ADDENDUM IS ISSUED AS A PART OF THE CONTRACT DOCUMENTS FOR THIS PROJECT AND AMENDS ONLY THOSE ITEMS SPECIFICALLY DEFINED HEREIN. THIS ADDENDUM MUST BE ATTACHED TO THE FRONT OF YOUR SET OF BID DOCUMENTS.

---

In preparing bids, the Bidder shall take into consideration the following items. Information shown herein supersedes requirements issued under previous dates.

ITEM NO. 1 **Additional Special Specification: Channel Toe Restoration**

The following Special Specification shall be added to Division III: Technical Specifications:

Part 306 – Special Specifications: Channel Toe Restoration

- 306.1 Prior to commencing any work related to the channel banks, Contractor shall install the Sag Pipe, and allow the Sag Pipe to drain the channel of sanding water.
- 306.2 Contractor shall reshape the toe to match original typical section as detailed in the plans (Sheet G3 – Typical sections. This may be accomplished by:
- a. Bringing in-situ soil lost from the toe to the channel back to the toe of the channel, or
  - b. Utilizing material from the City stockpile adjacent to the Haikey Creek Levee

# CITY OF BIXBY

*P.O. Box 70  
116 W. Needles Ave.  
BIXBY, OK 74008  
(918) 366-4430  
(918) 366-6373 (fax)*

This fill material shall be placed at the low point, in horizontal planes up to the finished grade using spreading and dishing equipment on each layer to obtain uniform moisture and thickness before compacting.

- 306.3 Soil shall be placed in lifts of no greater than 8 inches, and compacted to at least 95 percent of maximum density (AASHTO T 99 Methods C or D), within 2 percentage points of the optimum moisture content (AASHTO T 99).

